

Hochwasserrisikomanagementplan Fulda - hydraulische Berechnungen

Untere Eder Abschnitt 6 - tabellarische Ergebnisdarstellung

| Station [km] | Sohlhöhe [m ü. NN] | HQ ₅ [m ü. NN] | HQ ₁₀ [m ü. NN] | HQ ₂₀ [m ü. NN] | HQ ₅₀ [m ü. NN] | HQ ₁₀₀ [m ü. NN] | HQ ₁₀₀ * 1.3 [m ü. NN] |
|-----------------|-----------------------|------------------------------|-------------------------------|-------------------------------|-------------------------------|--------------------------------|--------------------------------------|
| 46,988 | 198,83 | 203,17 | 203,49 | 203,78 | 204,15 | 204,39 | 205,14 |
| 47,107 | 198,98 | 203,19 | 203,50 | 203,79 | 204,16 | 204,40 | 205,13 |
| 47,113 | 198,98 | 203,18 | 203,49 | 203,78 | 204,14 | 204,38 | 205,12 |
| 47,123 | 199,12 | 203,19 | 203,50 | 203,79 | 204,15 | 204,39 | 205,13 |
| 47,185 | 199,37 | 203,19 | 203,50 | 203,78 | 204,15 | 204,39 | 205,11 |
| 47,309 | 199,86 | 203,29 | 203,59 | 203,87 | 204,22 | 204,45 | 205,17 |
| 47,438 | 199,75 | 203,57 | 203,87 | 204,14 | 204,49 | 204,71 | 205,43 |
| 47,464 | 200,04 | 203,59 | 203,89 | 204,16 | 204,49 | 204,72 | 205,42 |
| 47,482 | 200,30 | 203,62 | 203,91 | 204,18 | 204,52 | 204,75 | 205,46 |
| 47,602 | 200,37 | 203,74 | 204,04 | 204,31 | 204,65 | 204,88 | 205,60 |
| 47,750 | 199,27 | 203,90 | 204,20 | 204,47 | 204,82 | 205,05 | 205,78 |
| 47,771 | 199,91 | 203,87 | 204,17 | 204,44 | 204,78 | 205,01 | 205,70 |
| 47,783 | 199,73 | 203,91 | 204,21 | 204,48 | 204,83 | 205,06 | 205,82 |
| 47,930 | 200,70 | 203,97 | 204,27 | 204,55 | 204,89 | 205,12 | 205,86 |
| 48,051 | 200,51 | 204,07 | 204,37 | 204,64 | 204,98 | 205,21 | 205,94 |
| 48,225 | 200,33 | 204,24 | 204,53 | 204,78 | 205,11 | 205,32 | 206,03 |
| 48,379 | 200,82 | 204,56 | 204,85 | 205,10 | 205,43 | 205,65 | 206,36 |
| 48,583 | 200,45 | 204,80 | 205,08 | 205,33 | 205,65 | 205,86 | 206,55 |
| 48,797 | 201,05 | 205,09 | 205,38 | 205,62 | 205,94 | 206,16 | 206,83 |
| 48,998 | 201,80 | 205,27 | 205,54 | 205,78 | 206,08 | 206,29 | 206,93 |
| 49,165 | 201,38 | 205,57 | 205,83 | 206,05 | 206,34 | 206,53 | 207,12 |
| 49,268 | 201,30 | 205,73 | 206,01 | 206,24 | 206,54 | 206,75 | 207,36 |
| 49,336 | 201,38 | 205,85 | 206,14 | 206,40 | 206,72 | 206,95 | 207,62 |
| 49,412 | 201,56 | 205,96 | 206,27 | 206,54 | 206,87 | 207,10 | 207,79 |
| 49,456 | 201,15 | 205,99 | 206,29 | 206,57 | 206,91 | 207,15 | 207,81 |
| 49,510 | 202,07 | 205,97 | 206,26 | 206,53 | 206,88 | 207,16 | 207,94 |

Hochwasserrisikomanagementplan Fulda
Untere Eder Abschnitt 6 - hydraulischer Längsschnitt

