

Hochwasserrisikomanagementplan Fulda - hydraulische Berechnungen

Obere Eder Abschnitt 3 - tabellarische Ergebnisdarstellung

Station [km]	Sohlhöhe [m ü. NN]	HQ ₅ [m ü. NN]	HQ ₁₀ [m ü. NN]	HQ ₂₀ [m ü. NN]	HQ ₅₀ [m ü. NN]	HQ ₁₀₀ [m ü. NN]	HQ ₁₀₀ * 1.3 [m ü. NN]
82,468	256,81	259,82	260,07	260,25	260,51	260,68	261,17
82,825	256,40	260,18	260,39	260,56	260,75	260,87	261,23
83,135	256,90	260,45	260,67	260,87	261,08	261,22	261,63
83,143	255,80	260,53	260,76	260,96	261,18	261,33	261,78
83,151	256,35	260,53	260,76	260,97	261,19	261,36	261,86
83,401	256,50	260,70	260,95	261,16	261,41	261,58	262,09
83,581	256,80	260,83	261,09	261,31	261,57	261,76	262,29
83,648	260,98	262,40	262,48	262,55	262,63	262,69	262,86
83,668	259,67	262,61	262,71	262,80	262,90	262,98	263,20
83,967	259,40	262,74	262,86	262,96	263,08	263,17	263,42
84,187	259,40	263,10	263,24	263,36	263,51	263,61	263,89
84,601	259,89	263,39	263,54	263,66	263,81	263,91	264,20
85,007	260,10	264,01	264,20	264,37	264,58	264,72	265,16
85,577	260,79	264,22	264,81	264,90	265,21	265,39	265,91
86,056	261,43	265,09	265,42	265,57	265,87	265,99	266,38
86,355	262,27	265,84	266,06	266,17	266,25	266,30	266,65
86,665	262,50	266,25	266,45	266,57	266,69	266,78	267,12
87,079	262,92	266,94	267,07	267,14	267,24	267,30	267,47
87,479	263,60	267,33	267,49	267,60	267,74	267,84	268,11
87,809	264,57	267,56	267,70	267,81	267,92	268,00	268,35
88,186	264,84	267,94	268,13	268,28	268,47	268,94	269,19
88,321	265,40	268,22	268,42	268,59	268,81	269,27	269,59
88,328	264,15	268,52	268,75	268,96	269,20	269,52	269,87
88,335	264,80	268,51	268,76	268,97	269,24	269,60	270,05
88,365	265,00	268,53	268,78	268,99	269,26	269,63	270,08
88,564	265,19	268,82	269,04	269,47	269,74	269,88	270,35
88,774	265,60	269,66	269,96	269,97	270,21	270,35	270,81
88,824	269,61	270,53	270,60	270,69	270,80	270,85	270,99
88,893	268,50	270,67	270,77	270,85	270,96	271,03	271,26
89,206	268,70	271,08	271,23	271,35	271,50	271,61	271,93
89,212	269,30	271,11	271,24	271,35	271,49	271,59	271,88
89,218	268,94	271,11	271,27	271,41	271,58	271,70	272,05
89,390	268,88	271,29	271,43	271,55	271,71	271,82	272,15

Hochwasserrisikomanagementplan Fulda
Obere Eder Abschnitt 3 - hydraulischer Längsschnitt

