

Hochwasserrisikomanagementplan Fulda - hydraulische Berechnungen

Haune Abschnitt 9 - tabellarische Ergebnisdarstellung

Station [km]	Sohlhöhe [m ü. NN]	HQ ₅ [m ü. NN]	HQ ₁₀ [m ü. NN]	HQ ₂₀ [m ü. NN]	HQ ₅₀ [m ü. NN]	HQ ₁₀₀ [m ü. NN]	HQ ₁₀₀ * 1.3 [m ü. NN]
33,966	251,12	253,74	253,89	253,94	254,01	254,05	254,12
34,032	251,22	253,26	254,01	254,08	254,17	254,24	254,38
34,118	251,29	254,05	254,32	254,42	254,56	254,66	254,86
34,233	251,76	254,31	254,49	254,58	254,78	254,98	255,21
34,339	252,10	254,66	254,85	255,01	255,25	255,42	255,69
34,352	252,42	254,62	254,80	254,92	255,19	255,33	255,66
34,365	252,40	254,62	255,07	255,20	255,36	255,47	256,14
34,436	252,48	255,08	255,38	255,55	255,76	255,91	256,46
34,464	253,19	255,41	255,66	255,82	256,03	256,18	256,66
34,475	253,09	255,37	255,62	255,79	256,00	256,15	256,64
34,491	253,36	255,54	255,67	255,81	255,99	256,13	256,61
34,518	253,41	255,52	255,62	255,73	255,86	255,95	256,35
34,530	253,44	255,54	255,67	255,86	256,11	256,31	256,87
34,541	253,44	255,79	255,95	256,13	256,37	256,56	257,08
34,614	253,90	255,81	255,98	256,15	256,39	256,57	257,09
34,683	253,93	255,90	256,04	256,19	256,41	256,59	257,10
34,763	253,95	256,02	256,09	256,23	256,44	256,61	257,11
34,837	253,93	256,24	256,34	256,40	256,53	256,67	257,13
34,879	254,09	256,38	256,44	256,53	256,58	256,67	257,15
34,993	254,38	256,69	256,78	256,86	256,95	257,02	257,24
34,999	254,34	256,75	256,80	256,85	256,97	257,05	257,28
35,010	254,33	256,90	256,96	257,02	257,09	257,15	257,33
35,068	254,48	256,95	257,03	257,10	257,18	257,25	257,43
35,156	254,67	257,03	257,12	257,19	257,29	257,36	257,54
35,239	254,73	257,17	257,25	257,32	257,40	257,46	257,63
35,378	254,69	257,34	257,41	257,47	257,55	257,61	257,75
35,466	254,67	257,49	257,54	257,59	257,66	257,71	257,85
35,525	255,10	257,64	257,69	257,74	257,82	257,87	258,00
35,604	255,66	257,90	257,95	258,07	258,14	258,19	258,30
35,766	255,88	258,14	258,20	258,40	258,45	258,49	258,59
35,828	255,79	258,19	258,25	258,43	258,48	258,52	258,62
35,918	256,05	258,57	258,61	258,64	258,68	258,70	258,76
35,971	256,11	258,72	258,78	258,83	258,89	258,93	259,02
36,049	256,19	258,92	258,99	259,05	259,10	259,13	259,23
36,204	256,79	259,17	259,25	259,31	259,38	259,42	259,80
36,278	257,07	259,24	259,32	259,38	259,46	259,51	259,84
36,373	257,43	259,59	259,64	259,70	259,77	259,82	259,99
36,490	257,80	259,89	259,94	259,98	260,04	260,09	260,19
36,556	258,00	260,00	260,04	260,09	260,16	260,21	260,32
36,695	258,42	260,46	260,54	260,59	260,64	260,67	260,75
36,837	258,84	260,99	261,02	261,06	261,10	261,15	261,25
36,914	259,07	261,38	261,42	261,45	261,50	261,53	261,60
36,949	259,15	261,46	261,52	261,56	261,62	261,66	261,77
37,082	259,29	261,78	261,81	261,88	261,97	262,03	262,29
37,148	259,33	261,86	261,90	261,97	262,04	262,09	262,29
37,174	259,35	261,90	261,95	262,01	262,07	262,10	262,18
37,204	259,36	262,00	262,10	262,22	262,37	262,48	262,79
37,261	259,64	262,07	262,12	262,26	262,42	262,53	262,84
37,325	259,96	262,26	262,33	262,43	262,54	262,63	262,90
37,397	260,04	262,41	262,45	262,49	262,61	262,70	262,95
37,504	260,17	262,95	263,00	263,04	263,09	263,13	263,20
37,550	261,58	263,27	263,32	263,35	263,40	263,43	263,52
37,570	261,04	263,41	263,46	263,51	263,57	263,62	263,71

Hochwasserrisikomanagementplan Fulda - hydraulische Berechnungen

Haune Abschnitt 9 - tabellarische Ergebnisdarstellung

Station [km]	Sohlhöhe [m ü. NN]	HQ ₅ [m ü. NN]	HQ ₁₀ [m ü. NN]	HQ ₂₀ [m ü. NN]	HQ ₅₀ [m ü. NN]	HQ ₁₀₀ [m ü. NN]	HQ ₁₀₀ * 1.3 [m ü. NN]
37,738	261,20	263,60	263,67	263,73	263,80	263,85	263,96
37,796	261,25	263,73	263,80	263,86	263,93	263,98	264,08
37,941	261,70	264,26	264,32	264,37	264,43	264,47	264,55
38,030	261,98	264,47	264,55	264,63	264,71	264,77	264,90
38,099	261,93	264,59	264,68	264,76	264,86	264,93	265,07
38,208	261,77	264,75	264,84	264,92	265,01	265,08	265,23
38,294	262,42	264,82	264,92	265,00	265,13	265,20	265,34
38,384	262,92	265,09	265,22	265,34	265,49	265,58	265,79
38,539	262,75	265,55	265,73	265,88	266,04	266,14	266,32
38,622	262,89	265,71	265,86	265,97	266,11	266,21	266,39
38,749	263,09	266,05	266,25	266,38	266,55	266,67	266,91
38,875	263,96	266,33	266,50	266,61	266,74	266,86	267,11
38,904	264,20	266,42	266,58	266,70	266,83	266,97	267,18
38,905	264,14	266,42	266,59	266,71	266,84	266,97	267,32
39,050	264,56	267,12	267,33	267,53	267,80	267,98	268,39
39,124	265,03	267,36	267,51	267,66	267,88	268,05	268,44
39,228	265,11	267,49	267,63	267,77	267,98	268,13	268,51
39,317	265,17	267,62	267,75	267,87	268,03	268,16	268,53
39,367	265,21	267,76	267,91	268,03	268,20	268,32	268,63
39,431	265,38	267,94	268,10	268,23	268,37	268,46	268,70
39,537	265,64	268,18	268,36	268,50	268,66	268,76	268,96
39,552	265,59	268,23	268,41	268,55	268,71	268,81	269,02
39,582	265,80	268,26	268,44	268,58	268,74	268,88	269,19
39,660	265,82	268,50	268,69	268,84	269,04	269,17	269,45
39,734	265,85	268,70	268,90	269,07	269,29	269,44	269,77
39,804	265,93	268,81	269,02	269,20	269,43	269,59	269,94
39,874	266,26	268,86	269,06	269,24	269,45	269,61	269,95
39,946	266,60	269,03	269,24	269,42	269,65	269,83	270,22
40,009	266,88	269,21	269,41	269,59	269,84	270,03	270,43
40,103	267,07	269,55	269,75	269,90	270,10	270,25	270,61
40,178	267,22	269,81	269,94	270,07	270,25	270,39	270,73
40,262	267,64	269,97	270,08	270,18	270,33	270,45	270,76
40,335	267,99	270,28	270,41	270,52	270,64	270,73	270,91
40,423	268,19	270,72	270,94	271,14	271,39	271,58	271,66
40,569	268,66	270,98	271,07	271,29	271,51	271,67	271,77
40,588	268,96	270,90	271,19	271,36	271,54	271,68	271,98
40,593	268,88	271,19	271,51	271,73	272,00	272,19	272,63
40,631	268,22	271,38	271,65	271,85	272,10	272,28	272,70

Hochwasserrisikomanagementplan Fulda
Haune Abschnitt 9 - hydraulischer Längsschnitt

