

Hochwasserrisikomanagementplan Fulda - hydraulische Berechnungen

Untere Schwalm Abschnitt 4 - tabellarische Ergebnisdarstellung

Station [km]	Sohlhöhe [m ü. NN]	HQ ₅ [m ü. NN]	HQ ₁₀ [m ü. NN]	HQ ₂₀ [m ü. NN]	HQ ₅₀ [m ü. NN]	HQ ₁₀₀ [m ü. NN]	HQ ₁₀₀ * 1.3 [m ü. NN]
10,908	168,44	171,12	171,38	171,54	171,64	171,71	171,86
11,019	168,34	171,22	171,47	171,61	171,76	171,85	172,10
11,103	168,23	171,33	171,59	171,75	171,90	172,02	172,21
11,206	168,46	171,43	171,68	171,84	172,01	172,13	172,33
11,277	168,59	171,51	171,77	171,93	172,05	172,15	172,31
11,335	168,87	171,64	171,85	172,04	172,22	172,34	172,51
11,411	169,08	171,76	171,97	172,14	172,32	172,43	172,60
11,464	169,35	171,78	172,00	172,18	172,36	172,47	172,66
11,542	169,51	171,85	172,07	172,24	172,42	172,54	172,75
11,597	169,63	171,88	172,06	172,20	172,37	172,46	172,65
11,648	169,82	171,98	172,18	172,35	172,53	172,64	172,84
11,667	169,89	172,03	172,23	172,41	172,60	172,70	172,91
11,760	170,19	172,19	172,38	172,56	172,78	172,91	173,17
11,782	169,58	172,22	172,43	172,58	172,78	172,93	173,19
11,796	169,37	172,18	172,39	172,57	172,78	172,92	173,21
11,864	169,33	172,35	172,55	172,72	172,91	173,04	173,32
11,915	169,58	172,39	172,58	172,75	172,95	173,07	173,35
11,970	169,56	172,43	172,62	172,79	172,99	173,11	173,39
12,046	170,19	172,45	172,63	172,79	172,99	173,12	173,40
12,117	170,25	172,57	172,73	172,89	173,07	173,19	173,47
12,180	170,30	172,69	172,86	173,00	173,17	173,28	173,54
12,281	170,39	172,85	173,00	173,14	173,32	173,43	173,66
12,364	170,46	173,02	173,17	173,29	173,49	173,58	173,75
12,437	170,43	173,17	173,35	173,51	173,72	173,83	174,07
12,604	170,79	173,44	173,63	173,80	174,01	174,13	174,38

Hochwasserrisikomanagementplan Fulda
Untere Schwalm Abschnitt 4 - hydraulischer Längsschnitt

